

LOCATION MAP
1" = 1 MILE

DESIGN / DEVELOPMENT PLANS
PRINTS ISSUED FOR:
• REVIEW

NO.	DATE	REVISIONS
1	7/27/04	S.C.D. COMMENTS OF 7-14-04
2	10/29/04	S.C.D. COMMENTS OF 8-21-04
3	11/23/04	EASEMENTS ADDED

SUSSEX COUNTY
ENGINEERING DEPARTMENT

DELAWARE

APPROVED BY
SUSSEX COUNTY,
SUSSEX COUNTY,
DATE

GMB
GEORGE, MILES & BUHR, LLC
ARCHITECTS & ENGINEERS
SALISBURY, BALTIMORE, LEWES, SEAFORD, YORK
www.gmbnet.com

THE COTTAGES AT
NEPTUNE CANYON

BROADKILL HUNDRED
SUSSEX COUNTY, DELAWARE

APPROVED
SUSSEX CONSERVATION DISTRICT
30' WIDE AGRICULTURAL FORESTED
BUFFER STRIP (OPEN SPACE) FOR & STORMWATER MANAGEMENT
Reviewed By: *[Signature]* Date: 12/1/04
Approved By: *[Signature]* Date: 12/1/04

RICHARD E. HUFF, JR. &
JOCELYN M. JENKINS

SWALE PROTECTION NOTES

1. INSTALL ENERGY DISSIPATION PER "PIPE INLET/OUTLET RIPRAP DETAIL" ON SHEET C3.2.
2. INSTALL ENERGY DISSIPATION PER "TYPICAL RIPRAPPED SWALE SECTION" ON SHEET C3.2.

**SITE PLAN AND
SEDIMENT AND
STORMWATER
MANGEMENT PLAN**

SCALE: 1" = 100'
DESIGN BY: JUS/JWK
DRAWN BY: JWK
CHECKED BY: JAS
GMB FILE: 2003260
DATE: JUNE 2004
DRAWING 4 OF 18

C1

1. REVIEW AND OR APPROVAL OF THE SEDIMENT AND STORMWATER MANAGEMENT PLAN SHALL NOT RELIEVE THE CONTRACTOR FROM HIS OR HER RESPONSIBILITIES FOR COMPLIANCE WITH THE REQUIREMENTS OF THE SEDIMENT AND STORMWATER REGULATIONS, NOR SHALL IT RELIEVE THE CONTRACTOR FROM ERRORS OR OMISSIONS IN THE APPROVED PLAN.
2. IF THE APPROVED PLAN NEEDS TO BE MODIFIED, ADDITIONAL SEDIMENT AND STORMWATER CONTROL MEASURES MAY BE REQUIRED AS DEEMED NECESSARY BY THE SUSSEX CONSERVATION DISTRICT.
3. THE SUSSEX CONSERVATION DISTRICT RESERVES THE RIGHT TO ENTER PRIVATE PROPERTY FOR PURPOSES OF PERIODIC SITE INSPECTION.
4. FOLLOWING SOIL DISTURBANCE OR REDISTURBANCE, PERMANENT OR TEMPORARY STABILIZATION SHALL BE COMPLETED WITHIN 14 CALENDAR DAYS AS TO THE SURFACE OF ALL PERIMETER SEDIMENT CONTROLS, TOPSOIL STOCKPILES, AND ALL OTHER DISTURBED OR GRADED AREAS ON THE PROJECT SITE.
5. ALL EROSION AND SEDIMENT CONTROL PRACTICES SHALL COMPLY WITH THE DELAWARE EROSION AND SEDIMENT CONTROL HANDBOOK 1989 OR LATEST EDITION.
6. CONTRACTOR SHALL MAINTAIN AND REPAIR ALL EROSION AND SEDIMENT CONTROL AND STORMWATER MANAGEMENT PRACTICES DAMAGED DURING UTILITY INSTALLATION.
7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTENANCE OF THE STORMWATER MANAGEMENT FACILITIES FOR THIS PROJECT DURING CONSTRUCTION. THE OWNERS ASSOCIATION SHALL HAVE PERPETUAL MAINTENANCE RESPONSIBILITY OF THE STORMWATER MANAGEMENT FACILITIES FOR THIS PROJECT AFTER CONSTRUCTION.
8. APPROVED PLANS REMAIN VALID FOR 3 YEARS FROM THE DATE OF AN APPROVAL.
9. AS-BUILT SURVEYS AND DRAWINGS ARE TO SUBMITTED TO THE DISTRICT WITHIN 60 DAYS OF STORMWATER MANAGEMENT FACILITY COMPLETION.
10. APPROVAL OF A SEDIMENT AND STORMWATER PLAN DOES NOT GRANT OR IMPLY A RIGHT TO DISCHARGE STORMWATER RUNOFF. THE OWNER/DEVELOPER IS RESPONSIBLE FOR ACQUIRING ANY AND ALL AGREEMENTS, EASEMENTS, ETC., NECESSARY TO COMPLY WITH STATE DRAINAGE AND OTHER APPLICABLE LAWS.
11. ANY DEVIATION FROM THE "SEQUENCE OF OPERATIONS" INDICATED ON THIS DRAWINGS SHALL BE APPROVED BY THE SEDIMENT CONTROL REPRESENTATIVE.
12. MINOR FIELD ADJUSTMENTS MAY BE MADE TO INSURE THE CONTROL OF SEDIMENT, UPON APPROVAL OF SEDIMENT CONTROL REPRESENTATIVE.
13. PLACEMENT AND INSTALLATION OF SEDIMENT CONTROL DEVICES SHALL ALLOW FOR FULL PROTECTION OF TRENCH EXCAVATION, STOCKPILES, AND OTHER AREAS DISTURBED DURING CONSTRUCTION PROCEDURES.
14. ALL SEDIMENT CONTROL DEVICES ONCE INSTALLED SHALL BE APPROVED BY SEDIMENT CONTROL REPRESENTATIVES BEFORE PROCEEDING WITH ACTUAL CONSTRUCTION.
15. AT THE END OF EACH WORKING DAY ALL SEDIMENT CONTROL DEVICES SHALL BE INSPECTED AND LEFT IN FUNCTIONAL CONDITION.
16. NO SPOILS, STOCKPILED OR EXCAVATED MATERIAL MAY BE DISCHARGED INTO WETLANDS REGULATED BY THE STATE OF DELAWARE OR THE U.S. ARMY CORPS OF ENGINEERS.
17. MATERIAL REMOVED FROM SURFACE TREATED, GRAVEL, OR SAND ROADS AND STOCKPILED FOR RE-USE SHALL BE PROTECTED WITH APPROVED SEDIMENT CONTROL PROCEDURES. THE METHOD PROPOSED SHALL BE REVIEWED WITH SUSSEX CONSERVATION DISTRICT REPRESENTATIVE PRIOR TO THE START OF CONSTRUCTION.
18. CONTACT SUSSEX CONSERVATION DISTRICT PRIOR TO COMMENCEMENT OF ANY WELL POINT OPERATIONS.
19. EROSION CONTROL MATTING IS REQUIRED IN OPEN CHANNELS AND ON SLOPES OF 3H:1V OR STEEPER. MATTING SHALL BE "NORTH AMERICAN GREEN SC150BN" OR AN EQUAL APPROVED BY THE SUSSEX CONSERVATION DISTRICT.
20. LOCATE STOCKPILES ON AREAS WITH LITTLE OR NO SLOPE. STOCKPILES MUST BE SURROUNDED WITH SILT FENCE OR A STABILIZED EARTHEN BERM.
21. STOCKPIILING OF EXCAVATED MATERIAL OUTSIDE OF THE CONTRACT AREA SHALL REQUIRE AN ADDITIONAL EROSION AND SEDIMENT CONTROL PLAN FOR THAT LOCATION. PLAN MUST BE SUBMITTED AND APPROVED BY THE SUSSEX CONSERVATION DISTRICT.
22. TO PREVENT OR REDUCE MOVEMENT OF DUST FROM DISTURBED SOIL SURFACES, THE CONTRACTOR SHALL SPRINKLE THE SITE WITH WATER UNTIL THE SURFACE IS MOIST AND REPEAT AS NECESSARY.
23. ALL GRADED AREAS TO BE SEEDED SHALL HAVE A 4" MINIMUM DEPTH OF TOPSOIL.
24. THE ENTIRE PROPERTY IS OUTSIDE THE 100 YEAR FLOOD ZONE, PER F.E.M.A. FIRM MAP NUMBER 10005C0325 F.
25. THE PREDOMINANT SOIL TYPES AT THE CONSTRUCTION SITE ARE SASSAFRAS SANDY LOAM, 0 TO 2 PERCENT SLOPES (S_{oa}), KENANSVILLE LOAMY SAND, 0 TO 2 PERCENT SLOPES (K_{ba}), RUMFORD LOAMY SAND, 0 TO 2 PERCENT SLOPES (R_{ua}), AND WOODSTOWN SANDY LOAM (W_o).
26. SEDIMENT EXCAVATED FROM THE POND DURING MAINTENANCE OPERATIONS WILL BE HAULED OFF-SITE WITHIN SEVEN (7) DAYS OF REMOVAL.
27. ALL LOT LINES ALONG THE ROAD SHALL HAVE A 15' WIDE DRAINAGE AND UTILITY EASEMENT ALONG THE INTERIOR SIDE.
28. SITE DATA (IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY THESE QUANTITIES):
SITE AREA: 85.87 ACRES
AREA TO BE DISTURBED: 16.7 ACRES IN PHASE ONE, 5.2 ACRES IN PHASE TWO
EARTH CUT VOLUME: ±28,400 CU. YDS. IN PHASE ONE, ±5,000 CU. YDS. IN PHASE TWO
FILL VOLUME: ±28,400 CU. YDS. IN PHASE ONE, ±5,000 CU. YDS. IN PHASE TWO

I, THE UNDERSIGNED, CERTIFY THAT ALL LAND CLEARING, CONSTRUCTION AND DEVELOPMENT SHALL BE DONE PURSUANT TO THE APPROVED PLAN AND THAT RESPONSIBLE PERSONNEL INVOLVED IN THE LAND DISTURBANCE WILL HAVE A CERTIFICATION OF TRAINING AT A DEPARTMENTAL SPONSORED OR APPROVED TRAINING PROGRAM FOR THE CONTROL OF EROSION AND SEDIMENT CONTROL BEFORE INITIATION OF THE PROJECT. I CERTIFY THAT THE DEPARTMENT OR DELEGATED INSPECTION AGENCY HAS THE RIGHT TO CONDUCT ON-SITE INSPECTIONS.

OCTOBER 28, 2004
DATE

STANDARD SYMBOL SCE

50' MINIMUM

3'

MOUNTABLE BERM (OPTIONAL)

EXIST. PAVEM.

3:1

3:1

6' MIN.

TREVIRA SPUNBOND 1135, MIRAFIT 600K, OR EQUIVALENT FILTER CLOTH

EXISTING GROUND

PROFILE

50' MIN.

10' MIN.

10' MIN.

EXISTING PAVEMENT

PLAN VIEW

1. **Stone size** - Use 2" stone, or reclaimed or recycled concrete equivalent.
2. **Length** - As required, but not less than 50 feet (except on a single residence lot where a 30 foot minimum length would apply).
3. **Thickness** - Not less than six (6) inches.
4. **Width** - Ten (10) Foot minimum, but not less than the Full width at points where ingress or egress occurs.
5. **Filter Cloth** - Will be placed over the entire area prior to placing of stone.
6. **Surface Water** - All surface water flowing or diverted toward construction entrances shall be piped across the entrance. If piping is impractical, a nountable berm with 5' slopes will be permitted.
7. **Maintenance** - The entrance shall be maintained in a condition which will prevent tracking or piping of sediments onto public rights-of-way. This may require periodic top dressing with additional stone as conditions demand and repair and/or cleanup of any resources used to trap sediment. All sediment spilled, dropped, washed or tracked onto public rights-of-way must be removed immediately.
8. **Washing** - Vehicle wheels shall be cleaned to remove sediment prior to entrance onto public rights-of-way. Washing is required at all entrances to a site on an area stabilized with stone and wire meshing into an approved sediment trapping device.
9. **Periodic inspection and needed maintenance** shall be provided after each rain.

SEEDBED PREPARATION:
LOOSEN UPPER 4 INCHES OF SOIL BY DISCING, RAKING, OR OTHER
ACCEPTABLE MEANS BEFORE SEEDING.

APPLY 1-2 TONS PER ACRE (46-92 LBS/1000 SQ. FT.) OF DOLOMITIC LIMESTONE AND 600 LBS PER ACRE (14 LBS/1000 SQ. FT.) OF 10-10-10 FERTILIZER.

FOR PERIODS OF SEPTEMBER 1 THROUGH NOVEMBER 15 AND MARCH 1 THROUGH MAY SEED WITH 40 LBS/ACRE OF PERENNIAL RYE (1.0 LBS/1000 SQ. FT.). PERIODS OF NOVEMBER 15 THROUGH FEBRUARY 28 PROTECT SITE BY APPLYING 2 TONS PR ACRE OF WELL ANCHORED STRAW MULCH AND SEED AS SOON AS POSSIBLE IN THE SPRING.

APPLY 1-1/2 TO 2 TONS PER ACRE (70 TO 90 LB/1000 SQ. FT.) OF UNROTTED SMALL GRAIN STRAW IMMEDIATELY AFTER SEEDING. ANCHOR MULCH IMMEDIATELY AFTER APPLICATIONS USING A SYNTHETIC BINDER SUCH AS ACRYLIC DLR (AGRI-TAC) DCA-70, PETROSET OR TERRA TACK AT RATES RECOMMENDED BY THE MANUFACTURER.

SEEDBED PREPARATION:
 LOOSEN UPPER 4 INCHES OF SOIL BY DISCING, RAKING, OR OTHER
 ACCEPTABLE MEANS BEFORE SEEDING.

APPLY 1-2 TONS PER ACRE (46-92 LBS/1000 SQ. FT.) OF DOLOMITIC LIME-
STONE AND 600 LBS PER ACRE (14 LBS/1000 SQ. FT.) OF 10-10-10
FERTILIZER.

FOR PERIODS OF SEPTEMBER 1 THROUGH NOVEMBER 15 AND MARCH 1 THROUGH MAY, SEED WITH 210-230 LBS PER ACRE (5 LBS/1000 SQ. FT.) OF KENTUCKY 31 TALL FESCUE. FOR PERIODS OF NOVEMBER 15 THROUGH FEBRUARY 28, PROTECT SITE BY APPLYING 2 TONS PER ACRE OF WELL ANCHORED STRAW MULCH AND SEED AS SOON AS POSSIBLE IN THE SPRING.

APPLY 1-1/2 TO 2 TONS PER ACRE (70 TO 90 LB/1000 SQ. FT.) OF UNROTTED SMALL GRAIN STRAW IMMEDIATELY AFTER SEEDING. FINCH MULCH IMMEDIATELY AFTER APPLICATIONS USING A SYNTHETIC BINDER SUCH AS ACRYLIC DLR (AGRI-TAC) DCA-70, PETROSET OR TERRA TACK AT RATES RECOMMENDED BY THE MANUFACTURER.

INSPECT ALL SEEDED AREAS AND MAKE NEEDED REPAIRS, REPLACEMENTS, AND RESEEDINGS.

THE SITE WAS INSPECTED BY ENVIRONMENTAL RESOURCES, INC. FOR THE EXISTENCE OF WETLANDS IN ACCORDANCE WITH FEDERAL 404 WETLAND JURISDICTIONAL DETERMINATION REQUIREMENTS. THE WETLANDS THAT WERE LOCATED ON-SITE ARE ISOLATED, NON-NAVIGABLE AND INTRASTATE AND ARE THEREFORE OUTSIDE THE JURISDICTION OF THE U.S. ARMY CORPS OF ENGINEERS.

Diagram illustrating the dimensions and flow direction for a filter system:

- 10' MAXIMUM CENTER TO CENTER (Distance between filter units)
- 36" MINIMUM LENGTH FENCE POST DRIVEN A MINIMUM OF 16" INTO GROUND (Post dimensions)
- 16" MINIMUM HEIGHT OF FILTER (Filter height)
- 8" MIN. (Minimum distance between filter units)
- FLOW (Direction of flow indicated by arrows)

Diagram illustrating the installation of a fence post section. The post is driven into the ground, with the filter cloth embedded 8 inches into the ground. The post section is driven a minimum of 16 inches into the ground. The ground is labeled as undisturbed ground. The flow direction is indicated by an arrow pointing right.

Labels in the diagram include:

- 36" MINIMUM FENCE POST LENGTH
- FILTER CLOTH
- FLOW
- EMBED FILTER CLOTH MIN. 8" INTO GROUND
- FENCE POST SECTION MINIMUM 20" ABOVE GROUND
- UNDISTURBED GROUND
- FENCE POST DRIVEN A MINIMUM OF 16" INTO THE GROUND
- SECTION

1.	Filter cloth to be fastened securely to fence posts with wire ties or staples.	Posts: Steel, either T or U, or 2" hardwood
2.	When two sections of filter cloth adjoin each other they should be overlapped by six inches and folded.	Filter Cloth: Poly Filter X, Mirafl 100x, stablinsa T40N or approved equivalent
3.	Maintenance shall be performed as needed and material removed when "bulges" develop in the silt fence.	Prefabricated Unit: Geofab, Envirofence, or approved equivalent

1. SUSSEX CONSERVATION DISTRICT MUST BE NOTIFIED IN WRITING FIVE (5) DAYS PRIOR TO COMMENCING WITH GRADATION. FAILURE TO DO SO CONSTITUTES A VIOLATION OF THE APPROVED SEDIMENT AND STORMWATER MANAGEMENT PLAN.
2. GRADING WITHIN PHASE TWO SHALL START UNTIL ALL GRADING AND STABILIZATION WITHIN PHASE ONE HAS BEEN COMPLETED, AND APPROVAL HAS BEEN GRANTED FROM THE SEDIMENT CONTROL INSPECTOR. DISTURBANCE OF GREATER THAN 20 ACRES WITHOUT PERMISSION FROM SUSSEX CONSERVATION DISTRICT CONSTITUTES A VIOLATION OF THE APPROVED SEDIMENT AND STORMWATER PLAN.
3. CLEAR AND GRUB THOSE AREAS NECESSARY FOR INSTALLATION OF SEDIMENT CONTROL MEASURES.
4. INSTALL STABILIZED CONSTRUCTION ENTRANCE.
5. INSTALL PERIMETER CONTROLS.
6. CLEAR AND GRUB REMAINING AREA (WITHIN LIMIT OF DISTURBANCE).
7. STRIP TOPSOIL AND STOCKPILE AT DESIGNATED LOCATIONS.
8. ROUGH GRADE POND, STOCKPILE AND TRANSPORT EXCAVATED MATERIAL TO REQUIRED ON-SITE LOCATIONS. POND SHALL BE USED AS TEMPORARY SEDIMENT BASINS DURING CONSTRUCTION. SEDIMENT POND NEEDS TO BE CLEANED OUT AFTER THE SITE IS STABILIZED, AND EXCAVATED TO FINAL GRADE. STABILIZE POND PER SEEDING NOTES ON THIS SHEET AND COVER ENTIRE SLOPE WITH EROSION CONTROL MATTING PLACED PER "TYPICAL MATTING INSTALLATION DETAIL" ON SHEET C3.
9. ROUGH GRADE ROADS AND INSTALL CULVERTS. SWALES WITH TEMPORARY STONE CHECK DAMS SHALL CONVEY STORMWATER TO THE SEDIMENT TRAP.
10. INSTALL UNDERGROUND UTILITIES.
11. INSTALL GRAVEL BASE COURSE AND PAVE ROADS.
12. TOPSOIL, FINE GRADE, SEED AND MULCH DISTURBED AREAS.
13. REMOVE SEDIMENT CONTROL MEASURES AND STABILIZE AREA AFTER OBTAINING PERMISSION FROM SEDIMENT CONTROL INSPECTOR.
14. REMOVE ACCUMULATED SEDIMENT FROM PONDS. GRADE PONDS TO FINAL GRADE AND STABILIZE.
15. AS-BUILT DRAWINGS FOR EACH POND SHALL BE SUBMITTED TO THE DISTRICT WITHIN 60 DAYS OF POND COMPLETION. THESE DRAWINGS AND ASSOCIATED COMPUTATIONS SHOULD VERIFY THAT THE CUMULATIVE AS-BUILT STORAGE IN THE PONDS AND THAT THE OUTLET STRUCTURE WILL ALLOW THE POND TO FUNCTION AS DESIGNED.
16. CONSTRUCT BUILDINGS AND CONNECT TO UTILITIES. NO HOUSE CONSTRUCTION CAN BEGIN UNTIL THE SUSSEX CONSERVATION DISTRICT HAS APPROVED THE CONSTRUCTION AND STABILIZATION OF THE STORMWATER FACILITIES.

The drawing consists of two parts: a cross-section labeled "SECTION B-B" and an elevation labeled "ELEVATION".

SECTION B-B: This view shows the vertical assembly. From top to bottom, it includes a "GEOTEXTILE" layer, a "WIRE MESH" layer, and a "POST". The distance between the geotextile and the wire mesh is labeled "6\" (TYP)". A note "SECURE WITH WIRE OR STAPLES" points to the connection between the geotextile and the wire mesh. A "FLOW" arrow points downwards on the left side.

ELEVATION: This view shows the horizontal layout. It features a grid of "6\"x6\" 14 GAGE WIRE MESH". A note "FASTEN GEOTEXTILE TO WIRE MESH AT 6\"c.c. (TYP.)" points to the intersections of the grid. A vertical dimension of "18\" MIN." is shown on the left, and a horizontal dimension of "6\"" is shown at the bottom. Arrows labeled "B" indicate the direction of the section cut.

POST

GEOTEXTILE

FASTENER (TYP.)

TEXTILE

NOTE:
THIS DEVICE IS INTENDED TO CONTROL SHEET
FLOW ONLY. IT SHALL NOT BE USED IN AREAS
OF CONCENTRATED FLOW.

CONNECTION DETAIL
FOR USE WITH JOINING TWO
ADJACENT SILT FENCE SECTIONS

PLAN SYMBOL
RSF

Diagram illustrating a proposed dwelling entrance structure. The structure is a rectangular box labeled "PROPOSED DWELLING". Below the dwelling, a "PROPOSED 10'x30' STABILIZED CONSTRUCTION ENTRANCE" is shown, which is a vertical structure filled with stones. To the left of the entrance, a "SILT FENCE" is indicated. The entrance is situated on a road surface, with a "CULVERT PIPE AS NECESSARY. PLACE AT LEAST 6" OF STONE OVER PIPE." shown below it. The road surface is marked with "S" and "S" on either side of the entrance. The "EDGE OF ROAD" is indicated on the right side. A "3' MIN. (TYP.)" dimension is shown for the road width on the left side.

1. FOR EACH LOT, STABILIZED CONSTRUCTION ENTRANCE, NECESSARY SILT FENCING, AND OTHER EROSION CONTROL DEVICES TO BE INSTALLED AFTER ROAD CONSTRUCTION AND STORMWATER MANAGEMENT FACILITIES HAVE BEEN ESSENTIALLY COMPLETE, AND THE SITE DETERMINED TO BE "STABILIZED" BY THE DISTRICT.
2. SILT FENCE IS TO BE PLACED DOWNSLOPE OF GROUND THAT COULD BE DISTURBED.
3. SILT FENCE REINFORCED WITH WELDED WIRE FABRIC IS TO BE PLACED ADJACENT TO WETLAND AREAS.

CURRENT OWNER: WILLIAM EDWARD PETTYJOHN
601 FEDERAL STREET
MILTON, DELAWARE 19968
TEL. (302) 684-4585
FAX: N/A

APPLICANT / CONTRACT OWNER / DEVELOPER: FRANCIS J. GONZON
8 SPINNAKER CIRCLE
LEWES, DELAWARE 19958
TEL. (302) 645-5800
FAX (302) 645-7313

[illegible]

SUSSEX COUNTY
ENGINEERING DEPARTMENT

SUSSEX COUNTY, DELAWARE


APPROVED BY _____

DATE _____

GMB
GEORGE, MILES & BUHR, LLC
ARCHITECTS & ENGINEERS
BALTIMORE • LEWIS • SEAFORD • YORK
www.gmbnet.com

**THE COTTAGES AT
NEPTUNE CANYON**


**BROADKILL HUNDRED
SUSSEX COUNTY, DELAWARE**




SCALE : NONE

DESIGN BY : JWK
DRAWN BY : JWK
CHECKED BY: JAS
CMB FILE : 20031

C2




OUTFALL STRUCTURE DETAIL - CONCRETE WEIR
NO SCALE




SECTION B-B

CHANNEL AND POND SLOPE INSTALLATION





STAPLE PATTERN GUIDE




NORTH AMERICAN GREEN EROSION CONTROL BLANKET
#SC150BN
14849 HIGHWAY 41 NORTH, EVANSVILLE, INDIANA 47711
USA 1-800-772-2040 CANADA 1-800-448-2040

TYPICAL MATTING INSTALLATION DETAIL
NO SCALE




SECTION SKIMMER DEWATERING DEVICE DETAIL
NO SCALE

EMERGENCY SPILLWAY DETAIL
NO SCALE




TYPICAL SWALE SECTION A-A
NO SCALE





- Construction Specifications**
- Swales and ditches shall be prepared in accordance with the construction specifications described in the Standards and Specifications for Earth Dike, Temporary Dike, Perimeter Dike/Swale, or Diversion.
 - The check dam shall be constructed of 4' to 8' riprap. The riprap shall be placed so that it completely covers the width of the channel.
 - The top of the check dam shall be constructed so that the center is approximately 6' lower than the outer edges, forming a weir that the water can flow across.
 - The maximum height of the check dam at the center of the weir must not exceed three (3) feet.
 - Maximum spacing between dams should be the distance in the channel where the toe of the upstream dam is at the same elevation as the top of the downstream dam.

CHECK DAM LOCATIONS (LEFT & RIGHT)
(CONTRACTOR MAY FIELD ADJUST AS NECESSARY)


MASSEY'S CANYON ROAD	WILMINGTON CANYON ROAD	BALTIMORE CANYON ROAD
1+25	3+50	1+00
8+00	4+10L	3+00
9+00	4+50R	4+00
11+00	7+00	6+00
15+50	9+00	8+00
	10+00	9+75
	11+00	11+15
	12+00	
	13+00	
	14+00	
	17+00	
	18+00	
	19+00	
	20+00	
	21+00	
	22+00	
	25+00	
	28+00	



S.W.M. POND SECTION B - B



S.W.M. POND SECTION C - C




DESIGN / DEVELOPMENT PLANS
PRINTS ISSUED FOR:
• REVIEW

DATE	REVISIONS
7/27/04	1. S.C.D. COMMENTS OF 7-14-04
10/29/04	2. S.C.D. COMMENTS OF 8-21-04

NO.	SUSSEX COUNTY ENGINEERING DEPARTMENT	DELAWARE	DATE
1			
2			



GMB
GEORGE, MILES & BUHR, LLC
ARCHITECTS & ENGINEERS
BALTIMORE • BALTIMORE • SEAFORD • YORK
www.gmbnet.com

THE COTTAGES AT NEPTUNE CANYON
BROADKILL HUNDRED
SUSSEX COUNTY, DELAWARE



SEDIMENT AND STORMWATER MANAGEMENT DETAILS AND SECTIONS


SCALE: AS SHOWN	C3.1
DESIGN BY: JLS, JWK	
DRAWN BY: JWK	
CHECKED BY: JAS	
GMB FILE: 2003260	
DATE: JUNE 2004	DRAWING 6 OF 18



- CONSTRUCTION SPECIFICATIONS**
1. THE SUBGRADE FOR THE RIPRAP SHALL BE PREPARED TO THE REQUIRED LINES AND GRADES AS SHOWN ON THE PLAN. ANY FILL REQUIRED IN THE SUBGRADE SHALL BE COMPACTED TO A DENSITY OF APPROXIMATELY THAT OF THE SURROUNDING UNDISTURBED MATERIAL.
 2. THE RIPRAP SHALL CONFORM TO THE GRADING LIMITS AS SHOWN ON THE PLAN.
 3. FILTER CLOTH SHALL BE PROTECTED FROM PUNCHING, CUTTING OR TEARING. ANY DAMAGE OTHER THAN AN OCCASIONAL SMALL HOLE SHALL BE REPAIRED BY PLACING ANOTHER PIECE OF CLOTH OVER THE DAMAGED AREA. ALL CONNECTING JOINTS SHOULD OVERLAP A MINIMUM OF 1 FOOT IF THE DAMAGE IS EXTENSIVE, REPLACE THE ENTIRE FILTER CLOTH.
 4. STONE MAY BE PLACED BY EQUIPMENT. RIPRAP SHALL BE PLACED IN A MANNER TO PREVENT DAMAGE TO THE FILTER CLOTH. HAND PLACEMENT WILL BE REQUIRED TO THE EXTENT NECESSARY TO PREVENT DAMAGE TO THE CONDUITS, STRUCTURES, ETC.

TYPICAL PIPE INLET / OUTLET RIPRAP DETAIL

NO SCALE



- CONSTRUCTION SPECIFICATIONS**
1. THE SUBGRADE FOR THE RIPRAP SHALL BE PREPARED TO THE REQUIRED LINES AND GRADES AS SHOWN ON THE PLAN. ANY FILL REQUIRED IN THE SUBGRADE SHALL BE COMPACTED TO A DENSITY OF APPROXIMATELY THAT OF THE SURROUNDING UNDISTURBED MATERIAL.
 2. THE RIPRAP SHALL CONFORM TO THE GRADING LIMITS AS SHOWN ON THE PLAN.
 3. FILTER CLOTH SHALL BE PROTECTED FROM PUNCHING, CUTTING OR TEARING. ANY DAMAGE OTHER THAN AN OCCASIONAL SMALL HOLE SHALL BE REPAIRED BY PLACING ANOTHER PIECE OF CLOTH OVER THE DAMAGED AREA. ALL CONNECTING JOINTS SHOULD OVERLAP A MINIMUM OF 1 FOOT IF THE DAMAGE IS EXTENSIVE, REPLACE THE ENTIRE FILTER CLOTH.
 4. STONE MAY BE PLACED BY EQUIPMENT. RIPRAP SHALL BE PLACED IN A MANNER TO PREVENT DAMAGE TO THE FILTER CLOTH. HAND PLACEMENT WILL BE REQUIRED TO THE EXTENT NECESSARY TO PREVENT DAMAGE TO THE CONDUITS, STRUCTURES, ETC.

TYPICAL RIPRAPPED SWALE SECTION

NO SCALE

DESIGN / DEVELOPMENT PLANS
PRINTS ISSUED FOR:
• REVIEW

NO.	REVISIONS	DATE
1	S.C.E.D. COMMENTS OF 8-21-04 (ENTIRE SHEET ADDED)	10/28/04

SUSSEX COUNTY
ENGINEERING DEPARTMENT

SUSSEX COUNTY,
DELAWARE

APPROVED BY


DATE

GMB

GEORGE, MILES & BUHR, LLC
ARCHITECTS & ENGINEERS
SALISBURY · LEWES · SEAFORD · YORK
www.gmbnet.com

**THE COTTAGES AT
NEPTUNE CANYON**

BROADKILL HUNDRED
SUSSEX COUNTY, DELAWARE






**SEDIMENT AND
STORMWATER
MANAGEMENT
DETAIL, SECTION,
AND
POND PLAN**

SCALE	: AS SHOWN
DESIGN BY	: JLS, JWK
DRAWN BY	: JWK
CHECKED BY	: JAS
GMB FILE	: 2003260
DATE	: JUNE 2004

C3.2

DRAWING 7 OF 18



DESIGN / DEVELOPMENT PLANS
PRINTS ISSUED FOR:
• REVIEW

[illegible]

SUSSEX COUNTY
ENGINEERING DEPARTMENT


SUSSEX COUNTY, DELAWARE

APPROVED BY _____

DATE _____



THE COTTAGES AT
NEPTUNE CANYON
BROADKILL HUNDRED
SUSSEX COUNTY, DELAWARE



OUTFALL SWALE PROFILES

SCALE : AS SHOWN	C4
DESIGN BY : JWK	
DRAWN BY : JWK	
CHECKED BY: JAS	
GMB FILE : 2003260	
DATE : JUNE 2004	DRAWING 8 OF 18